RESOURCE CONSERVATION DISTRICT OF BUTTE COUNTY

ADDENDUM TO RFP DOCUMENTS

ADDENDUM #1

Humbug Road Realignment Project, Bids Due Dec. 4, 2026

Addendum issued: 11/05/26

All Addenda can be found at: https://www.bcrcd.org/announcements

Addendum No. 1- The following changes to the Request for Proposals and clarifications are provided based on updated information and must be added/ considered when completing your submittal.

1) Page 4: Text stating:

"Proposals shall include the following originally signed documents:

- Proposal Form and references (Section 5)
- Non-Collusion Affidavit (Section 6)
- Fire Plan acknowledgement (Section 7)
- Bid Bond
- Certificate of Insurance (see required amounts, Section 4: Instructions To Firms, item 12.)
- Bidder Qualifications Form (Appendix E)"

Is modified to:

"Proposals shall include the following originally signed documents:

- Proposal Form and references (Section 5)
- Non-Collusion Affidavit (Section 6)
- Fire Plan acknowledgement (Section 7)
- Bid Bond
- Certificate of Insurance (see required amounts, Section 4: Instructions To Firms, item 12.)
- Bidder Qualifications Form (Appendix E).
- A signed Acknowledgement of Addendum form (found in Section 5) confirming you read and understood this addendum."

2) Section 5, Proposal Form [Entire section]

Is modified to the following 8 pages.

SECTION 5: PROPOSAL FORM

When filing out this proposal form, please use the bid assumptions listed below:

• The contract sum shall be deemed to include all costs necessary to complete the work and shall include any costs which may arise from any reasonable unforeseen difficulties or delays encountered during the project.

• Vegetation/brush removed during site grubbing will be added to large burn piles on the same Forest Service section. Exact location to be determined by USFS/BCRCD.

• Spoils generated from construction and not re-used as fill, will be deposited in a location on the same Forest Service section. The location will be determined by BCRCD and will allow the spoils to be used as fill at other stream crossing sites.

• All construction-related debris and refuse encountered within culvert replacement sites and designated grading areas (old culverts, concrete, fencing, abandoned tires, etc.) will be hauled away and properly disposed of by the selected contractor.

• The successful contractor will work under the direct supervision of RAR with assistance from BCRCD, USFS, and BCPW. All tasks listed in the construction specifications must be completed to our satisfaction.

• The selected contractor must abide by all permit requirements as directed by BCRCD and RAR and/or regulatory staff to ensure the project remains in environmental compliance.

• This project will take place within applicable summer construction windows as determined by regulatory agencies and weather conditions.

• Total estimated construction duration is 4-10 weeks.

• Materials: See the Design Plans and “Rock Availability” in Section 2. The contractor will be responsible for trucking rock to the site and working with the Project Engineer and materials tester to ensure the rock meets project specifications.

- Culverts and Erosion Control: All culvert materials will be purchased by the contractor. All erosion control materials (except seed) will be purchased by the contractor.

Humbug Road Realignment Project Proposal Form

Please submit a lump-sum quote for each of the subtasks below, unless otherwise directed. Attach as many additional sheets as necessary to show BCRCD your firm's assumptions and calculations. Please also attach a rate sheet showing hourly costs for all staff who will be involved in the project.

NOTE: It is the contractor's responsibility to comply with the fire plan (Appendix C) and BCRCD expects fire plan compliance costs will be integrated into each bid item.

Items are subject to removal via change order, based on BCRCD budget.

Items may be increased or decreased by up to 25% in quantity without changing per-unit price. If the total pay quantity of any item of work required under the Contract varies from the Proposal quantity by 25 percent or less, payment therefor will be made for the quantity of work performed at the Contract unit price. See General Conditions, Articles 10 and 11 for details.

Items 19 and 20 are add-alternate bid items. Bids will be evaluated and awarded based on base bid first, and if multiple base bids are within project budget, final award will be based on add-alternate bid.

There will be no negotiation in price, either upwards or downwards, due to fluctuations in fuel cost.

LF=Linear Feet

Item	Description	Quantity	Unit	Unit Price	Total
0	**Mobilization**		Lump Sum	$	$
1	**26N33:** Road **reconstruction** to an outsloped 18-foot-wide rocked road with a 2-foot-wide shoulder on the outboard edge; includes two (2) turnouts and nine (9) rolling dips. Include grubbing, within the limits of grading.	2,721	LF		
2	**Site 25:** 35" by 24" arched CMP with installation of RSP and Carsonite culvert markers, complete in place.	50	LF		
3	**Site 26:** 42" x 29" CMP pipe arch and accompanying culvert section rebuild with installation of RSP and Carsonite culvert markers,, complete in place.	60	LF		
4	**New Construction:** Outsloped 18-foot-wide rocked road with pit run subgrade, a 2-foot-wide shoulder on the outboard edge; includes two (2) turnouts and five (5) rolling dips. NOTE: For this segment only, the cost of grubbing goes in a separate bid item, bid item 5.	2,082	LF		

5	Cost of grubbing the new construction segment within the limits of grading. Assume trees have been felled and moved out of the way, but stumps remain.	2,082	LF		
6	**26N02:** Road reconstruction to an outsloped 18-foot-wide rocked road with 2-foot-wide shoulder on the outboard edge, inboard ditch with one (1) ditch relief culvert installation with dissipater rock and carsonite markers, nine (9) rolling dips and two (2) turnouts. Include grubbing, within the limits of grading.	2,666	LF		
7	**Site 94:** 30" round CMP and accompanying culvert section rebuild with installation of RSP and Carsonite culvert markers,, complete in place.	50	LF	$	$
8	**Site 95:** 12.8-foot by 8.3-foot CMP pipe arch (mitered) & accompanying culvert section rebuild with installation Carsonite culvert markers,complete in place. NOTE: For this crossing only, the cost of installing the RSP goes in a separate bid item.	80	LF		
9	**Site 95 RSP:** Excavation of channel per plans, installation and keying-in of 521 cy of Class V RSP.		Lump sum		
10	**Site 96: Sediment Basin:** See sheet C4, detail 11.				
11	**Site 97:** 81" by 59" CMP pipe arch (mitered) & accompanying culvert section rebuild with installation of RSP and Carsonite culvert markers,, complete in place.	80	LF		
12	**Site 98:** 57" by 38" CMP pipe arch, & accompanying culvert section rebuild with installation of RSP and Carsonite culvert markers, complete in place. See pages C10 and C12 in the design plans.	50	LF		

13	**Existing BU 91513:** The rebuilt Humbug Summit road will be an outsloped 18-foot-wide rocked road with a 2-foot-wide shoulder on each edge and an inboard ditch and with eleven (11) rolling dips and 1 (1) critical dip. Includes the installation of twelve (12) ditch relief culverts with dissipater rock and carsonite markers, complete in place.	1,929	LF		
14	**Site 99:** 24" CMP and accompanying culvert section rebuild with installation of RSP and Carsonite culvert markers, complete in place. See pages C14 and C15 in the design plans.	50	LF		
15	**Ditch relief culverts**: 30 LF each of 18" round CMP	13	each		
16	**Trash racks:** See page C4, detail 9 in the design plans.	4	each		
17	**Erosion control** measures sufficient to maintain compliance with all permit requirements.	1	Lump Sum		
18	**Signs:** all to be installed per Forest Service EM7100-15 Manual, Typ. **14a.** Forest Service vertical route markers (FM1-7V) reading "BU 91513" **14b.**Carsonite vertical road markers (CRM-375 white), 72" tall with reflector; MUTCD Road Sign W7-1A MUTCD Road Sign W7-39	 6 42 1 1	 each each each each		
19	**Traffic Control**	1	Lump Sum		
20	Application for **encroachment permi**t from Butte County	1	Lump Sum		
21	**Water truck**	1	Lump Sum		
22	**Rock:** Ensuring adequate supply of all rock and aggregate needed for the project, excluding class V RSP.	1	Lump sum		

23	Ensuring adequate supply of the class V RSP currently called for in the design plans, i.e., 521 cy.				
24	**Placing boulders** to deny vehicle access to Willow Cr Meadow	1	Lump Sum		
	BASE PROPOSAL PRICE			Sum of above:	
25	**Add/Alternate bid item 1:** Clearing of new road construction segment, 26N33, and 26N02 (to grading limits plus at least 10 feet either side).	1	Lump Sum		
	ALTERNATE PROPOSAL PRICE 1			From above plus item 20:	
26	**Add/Alternate bid item 2:** Decommissioning of "old" BU91513	2,069	LF		
	ALTERNATE PROPOSAL PRICE			From above plus items 20 and 21:	**$**

Total Amount (written in words)

_____

Authorized Contractor Signature Date

_____ _____

Contractor's Designated Representative

_____

Address

_____

_____

Telephone Number: _____

Cellphone Number: _____

LIST OF SUBCONTRACTORS

The Bidder shall list the name and address, Contractor license number, description of portion of work, Bid Item Numbers, Percentage, and DIR Registration Number of each subcontractor to whom the Bidder proposes to subcontract portions of the work, in an amount in excess of

a) one-half of 1 percent of the prime contractor's total bid, or,

b) ten thousand dollars ($10,000),

whichever is greater.

Business Name and Location	California Contractor License Number	Description of Portion of Work	Bid Items Numbers	Percentage of Bid Item Subcontracted	DIR Public Works Registration Number

Experience

List **at least three (3) road and/or bridge** construction projects that you recently completed (within the past five years) demonstrating similar tasks for a similar project in a similar setting. We are primarily interested in any projects where you worked directly with the Lassen National Forest and/or Butte County Public Works. List the project name, contract amounts, and contacts of contract officers.

1) Job/Project Name_____
   Owner_____ Year_____ Contract Amount_____
   Contact Name_____ Phone_____
   Project Description_____
   _____

2) Job/Project Name_____
   Owner_____ Year_____ Contract Amount_____
   Contact Name_____ Phone_____
   Project Description_____
   _____

3) Job/Project Name_____
   Owner_____ Year_____ Contract Amount_____
   Contact Name_____ Phone_____
   Project Description_____
   _____

4) Job/Project Name_____
   Owner_____ Year_____ Contract Amount_____
   Contact Name_____ Phone_____
   Project Description_____
   _____

RESOURCE CONSERVATION DISTRICT BUTTE COUNTY

ACKNOWLEDGEMENT OF RECEIPT OF ADDENDUM 1

Humbug Road Realignment Project: Bids Due Dec 4, 2026

The undersigned hereby acknowledges receipt of ADDENDUM #1, which changed Section 5 (the Bid Proposal Form) and Page 4 (in the Notice To Bidders). This addendum was issued November 5, 2026.

The undersigned furthermore acknowledges that they have received and read Response To Questions #1, issued November 5, 2026.

Please submit a signed copy of this page with your bid packet to acknowledge that you have read and understood the Addendum and the Response to Questions. Failure to acknowledge receipt of all addenda may disqualify the bidder.

Name of proposer: _____

Signature of proposer: _____

Date: _____

END OF SECTION 5

End of Addendum #1